U.S. DEPARTMENT OF HOMELAND SECURITY FEDERAL EMERGENCY MANAGEMENT AGENCY National Flood Insurance Program

ELEVATION CERTIFICATE

Important: Read the instructions on pages 1-9.

OMB No. 1660-0008

Expiration Date: July 31, 2015

SECTION A – PROPERTY INFORMATION			OR INSURANCE COMPANY USE		
A1. Building Owner's Name Stephen & Diane Zabinski			olicy Number:		
A2. Building Street Address (including Apt., Unit, Suite, and/or Bldg. No.) or P.O. Route and Box No. 115 N. 34 th Avenue			ompany NAIC Number:		
City Borough of Longport	State NJ ZIP Code 08		(sme)		
A3. Property Description (Lot and Block Numbers, Tax Parcel Nu Block 113 Lot 7	mber, Legal Description, etc.)		/ dla		
A4. Building Use (e.g., Residential, Non-Residential, Addition, Accessory, etc.) Residential A5. Latitude/Longitude: Lat. 39°19'15.2" Long. 74°31'17.2" Horizontal Datum: NAD 1927 NAD 1983 A6. Attach at least 2 photographs of the building if the Certificate is being used to obtain flood insurance. A7. Building Diagram Number 8 A8. For a building with a crawlspace or enclosure(s): A9. For a building with an attached garage: a) Square footage of crawlspace or enclosure(s) 1133 sq ft a) Square footage of attached garage 354 sq ft					
b) Number of permanent flood openings in the crawlspace or enclosure(s) within 1.0 foot above adjacent grade 7 c) Total net area of flood openings in A8.b 1400 sq in d) Engineered flood openings? Yes No b) Number of permanent flood openings in the attached garage within 1.0 foot above adjacent grade 2 c) Total net area of flood openings in A9.b 400 sq in d) Engineered flood openings? Yes No					
SECTION B – FLOOD IN	ISURANCE RATE MAP (FIRM	I) INFORMATION			
	2. County Name tlantic	B3 NJ	3. State		
B4. Map/Panel Number B5. Suffix B6. FIRM Index Date N/A	e B7. FIRM Panel Effective/Revised Date August 15, 1983	B8. Flood Zone(s) A8	B9. Base Flood Elevation(s) (Zone AO, use base flood depth)		
☐ FIS Profile ☐ FIRM ☐ Community Determined ☐ Other/Source: B11. Indicate elevation datum used for BFE in Item B9: ☐ NGVD 1929 ☐ NAVD 1988 ☐ Other/Source: B12. Is the building located in a Coastal Barrier Resources System (CBRS) area or Otherwise Protected Area (OPA)? ☐ Yes ☐ No Designation Date: ☐ CBRS ☐ OPA					
SECTION C – BUILDING ELEVATION INFORMATION (SURVEY REQUIRED)					
C1. Building elevations are based on: Construction Drawings* Building Under Construction* Finished Construction *A new Elevation Certificate will be required when construction of the building is complete. C2. Elevations – Zones A1–A30, AE, AH, A (with BFE), VE, V1–V30, V (with BFE), AR, AR/A, AR/AE, AR/A1–A30, AR/AH, AR/AO. Complete Items C2.a–h below according to the building diagram specified in Item A7. In Puerto Rico only, enter meters. Benchmark Utilized: NJRTCM-Ref 0273 Vertical Datum: N.A.V.D 1988 Indicate elevation datum used for the elevations in items a) through h) below. NGVD 1929 NAVD 1988 Other/Source: Datum used for building elevations must be the same as that used for the BFE.					
a) Top of bottom floor (including basement, crawlspace, or enclo	osure floor) 7.5		e measurement used. feet		
b) Top of the next higher floor	13.7		feet meters		
c) Bottom of the lowest horizontal structural member (V Zones of	65.6	√ 50-3 0-	feet meters		
 d) Attached garage (top of slab) e) Lowest elevation of machinery or equipment servicing the bui (Describe type of equipment and location in Comments) 	7. <u>5</u> ilding 13. <u>3</u>	100 miles	feet meters feet meters		
 f) Lowest adjacent (finished) grade next to building (LAG) g) Highest adjacent (finished) grade next to building (HAG) h) Lowest adjacent grade at lowest elevation of deck or stairs, ir 	$\frac{7.1}{7.7}$ ncluding structural support $\frac{6.7}{1.7}$		feet meters		
SECTION D – SURVEYOR, ENGINEER, OR ARCHITECT CERTIFICATION					
	its my best efforts to interpret the d	lata available. , Section 1001. on A provided by a	PLACE SEAL		
Certifier's Name Stephen C. Martinelli	License Number 300		HERE		
Title P.L.S. Company Name Stephen C.Martinelli Land Surveying					
Address 1217 S.Shore Road Suite 106 City Ocean View rev 7-21-14 State NJ ZIP Code 08230					
Signature Date 06-03-14	Telephone 609-390	-9618	_		

ELEVATION CERTIFICATE, page 2	
IMPORTANT: In these spaces, copy the corresponding information from Section A.	FOR INSURANCE COMPANY USE
Building Street Address (including Apt., Unit, Suite, and/or Bldg. No.) or P.O. Route and Box No. 115 N. 34th Avenue	Policy Number:

IMPORTANT: In these spaces, of	IMPORTANT: In these spaces, copy the corresponding information from Section A.		FOR INSURANCE COMPANY USE		
Building Street Address (including Apt., Unit, Suite, and/or Bldg. No.) or P.O. Route and Box No. 115 N. 34th Avenue			Policy Number:		
City Borough of Longport	State NJ	ZIP Code 08403	Company NAIC Number:		
SECTION	I D – SURVEYOR, ENGINEER, OR ARCH	HITECT CERTIFICATION	(CONTINUED)		
Copy both sides of this Elevation Cert	ificate for (1) community official, (2) insurance a	gent/company, and (3) buildin	g owner.		
Comments There are a total of 9 Smart Vents Model# 1540-510 & 1540-520 located in the foundation of the building, (7) in the crawl space and (2) in the Garage. (See Attached). Lowest machiney A/C Platform is located outside the Building, Elevation=13.3'. The Conversion from NGVD 29' to NAVD 88' Datum is -1.3'. Preliminary Work Map from FEMA Flood Zone (AE9). Bottom of HVAC ducts are at elevation Revision 7-21-14					
Signature	Date	e 6-03-14			
SECTION E – BUILDING ELEVATION INFORMATION (SURVEY NOT REQUIRED) FOR ZONE AO AND ZONE A (WITHOUT BFE)					
For Zones AO and A (without BFE), c and C. For Items E1–E4, use natural	omplete Items E1–E5. If the Certificate is intenc grade, if available. Check the measurement use	ded to support a LOMA or LOMed. In Puerto Rico only, enter r	//R-F request, complete Sections A, B, neters.		
 E1. Provide elevation information for the following and check the appropriate boxes to show whether the elevation is above or below the highest adjacent grade (HAG) and the lowest adjacent grade (LAG). a) Top of bottom floor (including basement, crawlspace, or enclosure) is					
	F – PROPERTY OWNER (OR OWNER'S		RTIFICATION		
	zed representative who completes Sections A, I				
or Zone AO must sign here. The stater	ments in Sections A, B, and E are correct to the		,		
Property Owner's or Owner's Authorize	ed Representative's Name				
Address	City	Stat	e ZIP Code		
Signature	Date	Tele	phone		
Comments			☐ Check here if attachments		
	SECTION G - COMMUNITY INFOR	RMATION (OPTIONAL)			
	or ordinance to administer the community's flood applicable item(s) and sign below. Check the me				
	vas taken from other documentation that has be elevation information. (Indicate the source and				
	d Section E for a building located in Zone A (with		unity-issued BFE) or Zone AO.		
G3. The following information (Item	ns G4–G10) is provided for community floodplain	n management purposes.			
G4. Permit Number	G5. Date Permit Issued	G6. Date Certificate Of C	ompliance/Occupancy Issued		
G7. This permit has been issued for: G8. Elevation of as-built lowest floor (in G9. BFE or (in Zone AO) depth of flood G10. Community's design flood elevation	ing at the building site:	nprovement feet meters feet meters feet meters	Datum Datum Datum		
Local Official's Name	Ti	tle			
Community Name		elephone			
Signature	D;	ate			
Comments					

FEMA Form 086-0-33 (7/12)

Check here if attachments.

ELEVATION CERTIFICATE, page 3

Building Photographs

See Instructions for Item A6.

IMPORTANT: In these spaces, copy the corresponding information from Section A.

Building Street Address (including Apt., Unit, Suite, and/or Bldg. No.) or P.O. Route and Box No.

115 N. 34th Avenue

City Borough of Longport

State NJ

ZIP Code 08403

FOR INSURANCE COMPANY USE

Policy Number:

Company NAIC Number:

If using the Elevation Certificate to obtain NFIP flood insurance, affix at least 2 building photographs below according to the instructions for Item A6. Identify all photographs with date taken; "Front View" and "Rear View"; and, if required, "Right Side View" and "Left Side View." When applicable, photographs must show the foundation with representative examples of the flood openings or vents, as indicated in Section A8. If submitting more photographs than will fit on this page, use the Continuation Page.





Front View

6-2-14

Rear View

6-2-14





6-2-14



Smart Vent

6-2-14





ICC-ES Evaluation Report

ESR-2074

Reissued December 1, 2012 This report is subject to renewal February 1, 2015.

www.icc-es.org | (800) 423-6587 | (562) 699-0543

A Subsidiary of the International Code Council®

DIVISION: 08 00 00—OPENINGS Section: 08 95 00—Vents

REPORT HOLDER:

SMARTVENT PRODUCTS, INC. 450 ANDBRO DRIVE, SUITE 2B PITMAN, NEW JERSEY 08071 (856) 307-1468 www.smartvent.com eval@smartvent.com

EVALUATION SUBJECT:

SMART VENT® AUTOMATIC FOUNDATION FLOOD VENTS: FLOODVENT™ MODEL #1540-520; FLOODVENT™ STACKING MODEL #1540-521; SMARTVENT™ MODEL #1540-510; SMARTVENT™ STACKING MODEL #1540-511; WOOD WALL FLOOD MODEL #1540-570; WOOD WALL FLOOD OVERHEAD DOOR MODEL #1540-574; FLOODVENT™ OVERHEAD DOOR MODEL #1540-524; SMARTVENT™ OVERHEAD DOOR MODEL #1540-514

1.0 EVALUATION SCOPE

Compliance with the following codes:

- 2009 and 2006 International Building Code® (IBC)
- 2009 and 2006 International Residential Code® (IRC)

Properties evaluated:

- Physical operation
- Water flow

2.0 USES

The Smart Vent® units are automatic foundation flood vents (AFFVs) employed to equalize hydrostatic pressure on nonfire-resistance-rated foundation walls, rolling-type overhead doors and building walls subject to rising or falling flood waters. The Smart Vent® units are intended for use where flood hazard areas have been established in accordance with IBC Section 1612.3 or IRC Section R3222.1. Certain models also allow natural ventilation in accordance with Section 1203 of the IBC or Section 408.1 of the IRC.

3.0 DESCRIPTION

3.1 General:

When subjected to pressure from rising water, the Smart Vent[®] AFFVs disengage, then pivot open to allow flow in either direction to equalize water level and hydrostatic pressure from one side of the foundation to the other. The

AFFV pivoting door is normally held in the closed position by a buoyant release device. When subjected to rising water, the buoyant release device causes the unit to unlatch, allowing the plate to rotate out of the way and allow flow. The water level stabilizes, equalizing the lateral forces. Each unit is fabricated from stainless steel, and each opening provides 76 square inches (49 032 mm²) of net free area for flood mitigation in the open position. The SmartVENT™ Stacking Model #1540-511 and FloodVENT™ Stacking Model #1540-521 units each contain two vertically arranged openings per unit, providing 152 square inches (98 064 mm²) of net free area for flood mitigation in the open position.

3.2 Engineered Opening:

The AFFVs comply with the design principle noted in Section 2.6.2.2 of ASCE/SEI 24 for a maximum rate of rise and fall of 5.0 feet per hour (0.423 mm/s). In order to comply with the engineered opening requirement of ASCE/SEI 24, Smart Vent AFFVs must be installed in accordance with Section 4.0.

3.3 Model Sizes:

The FloodVENT™ Model #1540-520, SmartVENT™ Model #1540-510, FloodVENT™ Overhead Door Model #1540-524, and SmartVENT™ Overhead Door Model #1540-514 units measure 15³/₄ inches wide by 7³/₄ inches high (400 by 196.9 mm). The Wood Wall Flood Model #1540-570 and Wood Wall Flood Overhead Door Model #1540-574 units measure 14 inches wide by 8³/₄ inches high (355.6 by 222.25 mm). The SmartVENT™ Stacking Model #1540-511 and FloodVENT™ Stacking Model #1540-521 units measure 16 inches wide by 16 inches high (406.4 by 406.4 mm).

3.4 Ventilation:

The SmartVENT® Model #1540-510 and SmartVENT® Overhead Door Model #1540-514 both have screen covers with ¹/₄-inch-by-¹/₄-inch (6.35 by 6.35 mm) openings, yielding 51 square inches (32 903 mm²) of net free area to supply natural ventilation. The SmartVENT™ Stacking Model #1540-511 consists of two Model #1540-510 units in one assembly, and provides 102 square inches (65 806 mm²) of net free area to supply natural ventilation. Other AFFVs recognized in this report do not offer natural ventilation.

4.0 INSTALLATION

SmartVENT® and FloodVENT™ are designed to be installed into walls or overhead doors of existing or new construction from the exterior side. Installation of the vents must be in accordance with the manufacturer's



instructions, the applicable code and this report. The mounting straps allow mounting in wood, masonry and concrete walls up to 12 inches (305 mm) thick. In order to comply with the engineered opening design principle noted in Section 2.6.2.2 of ASCE/SEI 24, the Smart Vent® AFFVs must be installed as follows:

- With a minimum of two openings on different sides of each enclosed area.
- With a minimum of one AFFV for every 200 square feet (18.6 m²) of enclosed area, except that the SmartVENT™ Stacking Model #1540-511 and FloodVENT™ Stacking Model #1540-521 must be installed with a minimum of one AFFV for every 400 square feet (37.2 m²) of enclosed area.
- Below the base flood elevation.
- With the bottom of the AFFV located a maximum of 12 inches (305.4 mm) above grade.

5.0 CONDITIONS OF USE

The Smart Vent® AFFVs described in this report comply with, or are suitable alternatives to what is specified in, those codes listed in Section 1.0 of this report, subject to the following conditions:

- 5.1 The Smart Vent® AFFVs must be installed in accordance with this report, the applicable code and the manufacturer's installation instructions. In the event of a conflict, the instructions in this report govern.
- 5.2 The Smart Vent® AFFVs must not be used in the place of "breakaway walls" in coastal high hazard areas, but are permitted for use in conjunction with breakaway walls in other areas.

6.0 EVIDENCE SUBMITTED

Data in accordance with the ICC-ES Acceptance Criteria for Automatic Foundation Flood Vents (AC364), dated October 2007.

7.0 IDENTIFICATION

The Smart VENT® models recognized in this report must be identified by a label bearing the manufacturer's name (Smartvent Products, Inc.), the model number, and the evaluation report number (ESR-2074).

DIAGRAM 7

All buildings elevated on full-story foundation walls with a partially or fully enclosed area below the elevated floor. This includes walkout levels, where at least one side is at or above grade. The principal use of this building is located in the elevated floors of the building.

Distinguishing Feature — For all zones, the area below the elevated floor is ericlosed, either partially or fully. In A Zones, the partially or fully enclosed area below the elevated floor is with or without openings* present in the walls of the ericlosure. Indicate information about enclosure also and openings in Section A — Property Information.




DIAGRAM:8

All buildings elevated on a crawispace with the floor of the crawispace at or above grade on at least one side, with or without an attached garage.

Distinguishing Festure — For all zones, the sine below the first floor is enclosed by solid or partial perimeter wats. In all A zones, the creations is with or without openings' present in the wats of the crimetopace. Interest information about crawispace size and openings in Bection A — Private Information.





DIAGRAM 9

All buildings (other than split-level) elevated on a subgrade crawlspace, with or without attached garage.

Distinguishing Feature — The bottom (crawispace) floor is at or below ground level (grade) on all sides. If it the distance from the crawispace floor to the top of the next higher floor is more than 5 feet, or the crawispace floor is more than 2 feet below the grade (LAG) on all sides, use Diagram 2.)



- An "opening" is a permanent opening that allows for the free passage of water automatically in both directions without human intervention. Under the NFP, a minimum of two openings is required for enclosures or crawispaces. The openings shall provide a total net area of not less than one square inch for every square foot of area enclosed, excluding any bars, louvers, or other covers of the opening. Alternatively, an Individual Engineered Mood Openings Certification or an Evaluation Report issued by the International Code Council Evaluation Service (ICC ES) must be submitted to document that the design of the openings will allow for the automatic equalization of hydrostatic flood forces on exterior wills. A window, a door, or a garage door is not considered an opening; openings may be installed in doors. Openings shall be on at least two sides of the enclosed area. If a building has more than one enclosed area, each area must have openings to allow floodwater to directly enter. The bettom of the openings must be no fligher than one foot above the higher of the exterior or interior grade or floor immediately below the opening. For more guidance on openings, see NFIP Technical Bulletin 1
- A floor that is below ground level (grade) on all sides is considered a basement even if the floor is used for living purposes, or as an office, garage, workshop, etc.

